ENGINEERING DEPARTMENT.

MYSORE PUBLIC WORKS DEPARTMENT.

SPECIAL WATER-SUPPLY CONSTRUCTION DIVISION.

Dated 8th June 1925.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water-Supply Construction Division, up to 2 P.M. on 6th July 1925 for improving Water-Supply to Magadi Town, Bangalore District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1926.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M. on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees two hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving Water-Supply to Magadi Town," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for lumpsum items in the sanctioned estimate and for items for which there is no provision in the estimate shall be those that will be fixed by the Executive Engineer, either as per schedule of rates prevailing in market or as per data worked out with not more than 10 per cent for contractor's profit.

Tenders for improving Water Supply to Magadi Town.

Serial No.	Items of work	Unit	Quantity
	I. RAISING THE CROSS BUND AND EXTENDING THE EXISTING SLUICE.		
1	Earthwork excavation for foundation of revetment and removing the excavated earth for forming a bund with watering and tamping the same.	C.yd.	478
2	Gravel backing to revetment	"	400
3	Rough stone revetment with new stones	"	10·51
4	Turfing	S.yd.	160
5	Putting ring bund and removing the same again after the work is over (earth to be taken from the bed of tank).	C.yd.	889
6	Turfing the ring bund	S.yd.	400
	EXTENDING THE EXISTING SLUICE.		
1	Earthwork excavation cutting bund and refilling with watering and tamping ..	C.ydr	300
2	Stone jelly concrete in surki mortar	C.ft.	75
3	Burnt brick in surki mortar	"	150
4	Plastering with surki mortar	Sqr.	2·00
5	Covering with burnt stone slabs of 6" thick and cement pointing	S.ft.	200
6	Preparing and fixing jolly wood plug for the sluice with 1" iron rod and locking arrangement, complete	No.	1

Serial No.	Items of work	Unit	Quantity
	II. FIXING A SCOUR PIPE IN THE BED OF GOWRAMMANKERE.		
1	Earthwork, cutting bund with ½ to 1 slope (earth to be thrown on the rear slope of bund and used for backing the slope of the steps for the proposed pond behind the tank).	C.yd.	423
2	Re-filling the excavated portion with watering and tamping (earth to be taken from the bed of tank marked 'A' in the plan with 200' lead.	,,	423
3	Removing and re-setting old stone revetment with new jelly	,,	33
4	Gravel backing ½ mile lead	,,	16
5	Stone jelly concrete in surki mortar	C.ft.	151
6	Burnt brick in surki mortar	,,	188
7	Plastering with surki mortar	Sqr.	0·06
8	Burnt stone slabs 4½" to 6" thick roughly dressed	S.ft.	96
9	Fixing 9" sluice valve with rubber washers, bolts and nuts	No.	1
10	Laying and jointing 9" cast iron pipe with cement joints	R.ft.	105
11	Turfing	S.yd.	87
12	Rough stone apron with new stones	C.yd.	27
13	Gravelling the top of bund with watering and tamping ½ mile lead	,,	9
14	Fixing manhole cover with frame 2½' x 2½' after drilling holes	No.	1
	III. PUTTING AN INLET PIPE TO THE PROPOSED POND.		
1	Earthwork cutting bund and re-filling with watering and tamping in rear of proposed pond.	C.yd.	478
2	Putting ring bund and removing the same after the work is over with 1½ to 1 slope (earth to be taken from the bed of the tank marked 'A' in the plan including about 200 ft. lead and 20 ft. lift).	,,	12 44
3	Removing and resetting old stone revetment with new jelly	,,	21
4	Gravel backing ½ milelead	,,	15
5	Stone jelly concrete in surki mortar	C.ft.	107
6	Burnt brick in surki mortar	,,	248
7	Plastering with surki mortar	Sqr.	1·24
8	Burnt stone slabs 4½" to 6" thick roughly dressed	S.ft.	48
9	Turfing	S.yd.	45
10	Gravelling the top of bund with watering and tamping	C.yd.	6
11	Fixing 6" cast iron sluice valve with rubber washers bolts and nuts	No.	1
12	Laying and jointing 6" cast iron pipe with cement joints	R.ft.	185
13	Fixing manhole cover with frame 2½' x 2½' after drilling holes, etc.	No.	1
	IV. REMOVING SILT IN THE BED OF GOWRAMMANKERE.		
1	Removing silt in the bed of tank marked 'A' in plan and throwing on the rear slope of bund including baling out of water, if necessary.	C.yd.	2,499
2	Clearing the weeds in the bed of tank marked A and B in plan and removing it away from the site.	Sqr.	..
3	Clearing the lantana on the front slope of bund and removing it away from the site.	S.yd.	1,978
4	Rough stone revetment with new stones	C.yd.	67
5	Earthwork to bund including water and tamping (earth to be taken from the bed of tank marked A and B in the plan whichever convenient including about 100 ft. lead and 20 ft. lift	,,	1,379
6	Removing and resetting old stone revetment with new jelly packing	,,	112
7	Gravel backing ½ mile lead	,,	74
	V CONSTRUCTING A NEW POND BEHIND THE TANK.		
1	Earthwork excavation and throwing and forming the earth around the site including baling out water, if necessary	C.yd.	14
2	Burnt stone slabs for steps 6" thick roughly dressed	S.ft.	3,060
3	Rough stone revetment with new stones	C.yd.	08
4	Gravel backing	,,	34
5	Stone jelly concrete in surki mortar	C.ft.	190
	CONSTRUCTING VALVE CISTERN.		
1	Earthwork excavation and throwing and forming the earth around the site including baling out water, if necessary	C.yd.	8
2	Stone jelly concrete in surki mortar	C.ft.	56
3	Burnt brick in surki mortar	,,	90
4	Plastering with surki mortar	Sqr.	0·54
5	Burnt stone slabs 4½" to 6" thick roughly dressed	S.ft	106
6	Repairing the road with metal and consolidating	,,	120
7	New stone apron with jelly packing	C.yd.	18
8	Fixing 6" sluice valve with rubber washers, bolts and nuts	No.	1
9	Laying and jointing 6" cast iron pipe with cement joints	R.ft.	190
10	Fixing manhole cover with frame 2½' x 2½' after drilling holes	No.	1
	VI. CONSTRUCTING A MASONRY WALL ACROSS THE WEIR HALLA.		
1	Earthwork excavation including baling out water, if necessary, and throwing and forming the earth around.	C.yd.	36
2	Stone jelly concrete in mortar	C.ft.	95
3	Burnt stone in mortar	,,	288
4	Burnt brick in mortar	C.ft.	122
5	Burnt stone slabs 6" thick roughly dressed	S.ft.	78
6	Joggle joints with iron clamps and fixing with lead after drilling holes in the slab.	No.	2
7	Rough stone apron with new stones	C.yd.	24
8	Plastering with surki mortar	Sqr.	1·08

Notice dated 8th June 1925.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water Supply Construction Division, up to 2 P.M. of 6th July 1925, for carting cast iron and other materials from Tumkur Railway Station to Water Supply Work Site. An approximate estimate of quantities is given below. These quantities are not guaranteed. The specification and conditions for the work may be seen in the office during working hours.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

2 (*a*). The unloading and carting should be attended to immediately after the materials arrive allowing no room for demurrage and breakage. Losses in consequence of any delay in executing the order will have to be made good by the contractor.

3. Each tender must be accompanied by a deposit of Rs. 200 (rupees two-hundred only) in cash or Government promissory notes, as earnest money, and be superscribed "Tender for carting materials from Tumkur Railway Station to Water Supply Work Site," in default of which, tenders will be rejected.

4. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

6. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

7. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

STATEMENT.

No.	Description of work	Unit of work	Quantities
1	Unloading materials from the Wagons at the Tumkur Railway Station.	Railway maund ...	27,000
2	Carting to work site including loading, unloading and stacking.	Per mile per Railway maund.	27,000

N.B.—Fractions of a mile in excess of half a mile will be regarded as one mile, while those of half a mile and less shall be neglected in the calculation of the distance carted.

H. F. MAREER,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

DEPARTMENT OF AGRICULTURE.

No. 832-S., *dated 6th June* 1925.

In continuation of the Notification No. 805 of 24-25, dated the 6th May 1925, calling for applications for admissions to the Hebbal Agricultural School, published on page 525, Part IV of the *Mysore Gazette*, the applicants are informed that the preliminary Entrance Examination will be held in the Office of the Director of Agriculture at Bangalore and in the Offices of the Deputy Commissioners of other Districts at 11 A.M., on Saturday the 27th June 1925. The applicants that seek admission to the school are requested to attend.

GUNDAPPA, S. KURPAD,
Vice-Principal.